BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No. RRND/EE/Tend/04/2022-23, Date: 07.07.2022

Indet No: BBMP/2022-23/OW/WORK_INDENT52453

SCHEDULE -B

Name of Work: Providing Gallery to Musical Fountain in JP Park in Ward No 17 and Drilling of Borewells, Providing Water Supply and Construction of RO Plants in Rajarajeshwari nagara Constituency under PACKAGE- 2022-23 RRN-DIV-(10)

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	2377.08	Earth work excavation by manual means for drains,canals, waste weir draft, approach channels, key trench, foundation of Bridges and such similar works, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, excavated surface leveled and sides neatly dressed disposing off or leveling the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage & other appurtenances required to complete the work. In ordinary/soft rock without blasting upto 1.5 m depth	Cum	263.00	Rupees Two Hundred Sixty Three Only
2	280.01	Providing and laying in position plain cement concrete Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately)	Cum	6384.00	Rupees Six Thousand Three Hundred Eighty Four Only
3	167.04	KSRB 2.8 Providing and filling in foundation with granite/trap broken metal of 100 MM and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour charges and with all lead and lift etc complete as per specification and the direction of the Engineer in charge	Cum	2944.00	Rupees Two Thousand Nine Hundred Forty Four Only
4	518.28	Providing and laying in position Reinforced cement concrete M25 Using 20 mm nominal size graded crushed coarse aggregates for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement &	Cum	7680.00	Rupees Seven Thousand Six Hundred Eighty Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner

5	114.51	Providing and laying in position Reinforced cement concrete M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/ trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately)	Cum	7822.00	Rupees Seven Thousand Eight Hundred Twenty Two Only
6	519.56	Providing and laying in position Reinforced cement concrete M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/ trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately)	Cum	8533.00	Rupees Eight Thousand Five Hundred Thirty Three Only
7	197.34	Supplying, Fitting and Placing TMT Fe 500 & above Reinforcement in Foundation / Substructure / Superstructure complete as per Drawing and Technical Specifications.	Tonne	96634.00	Rupees Ninety Six Thousand Six Hundred Thirty Four Only
8	249.61	Earth work excavation by manual means for drains,canals, waste weir draft, approach channels, key trench, foundation of Bridges and such similar works, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, excavated surface leveled and sides neatly dressed disposing off or leveling the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage & other appurtenances required to complete the work. In ordinary/soft rock without blasting upto 1.5 m depth	Cum	263.00	Rupees Two Hundred Sixty Three Only
9	50.45	Providing and laying in position plain cement concrete Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement &	Cum	6384.00	Rupees Six Thousand Three Hundred Eighty Four Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner

10	39.37	Providing and laying in position Reinforced cement concrete M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately)	Cum	7407.00	Rupees Seven Thousand Four Hundred Seven Only
11	9.72	Providing and laying in position Reinforced cement concrete M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/ trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately)	Cum	7910.00	Rupees Seven Thousand Nine Hundred Ten Only
12	43.25	Providing and laying in position Reinforced cement concrete M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/ trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately)	Cum	8630.00	Rupees Eight Thousand Six Hundred Thirty Only
13	11.54	Supplying, Fitting and Placing TMT Fe 500 & above Reinforcement in Foundation / Substructure / Superstructure complete as per Drawing and Technical Specifications.	Cum	96634.00	Rupees Ninety Six Thousand Six Hundred Thirty Four Only
14	93.62	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	6152.00	Rupees Six Thousand One Hundred Fifty Two Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner

15	578.25	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x200x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	Sqm	1375.00	Rupees One Thousand Three Hundred Seventy Five Only
16	1424.43	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonary including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	344.00	Rupees Three Hundred Forty Four Only
17	114.84	Providing 12 mm cement plaster with cement mortar 1:4 (1 cement: 4 fine sand) to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge..	Sqm	245.00	Rupees Two Hundred Forty Five Only
18	1539.27	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two coat applied @ 1.67 ltr/10 m^2 over and including priming coat of exterior primer applied @ 2.20 kg/10 m^2) with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	156.00	Rupees One Hundred Fifty Six Only
19	128.34	Providing and laying water proofing treatment to the Roof with PU based single component elastomeric pure polyurethane based coating on New terrace/Chajjas/Sunken portion of WC:Bathroom, cold applied PU waterproofing membrane that is highly elastic with elongation greater than 400% and tensile strength greater than 2MPa as per ASTM D412. The waterproofing membrane to be applied in 2coats @ 1.6kg per m2 to achieve final DFT (dry film thickness) of 1mm including prime coat of epoxy primer @150 g per m2 and protection with 120gsm Geo-textile over the waterproofing membrane. The finished cost to include surface preparation, making coving at Junction, Bore Packing, treatment of construction joints completely as per specification & with a 10 years warranty on product & work from certified manufacturers as per the direction of the Engineer In charge.	Sqm	856.00	Rupees Eight Hundred Fifty Six Only
20	384.93	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ m2 including grouting the joints with white cement and matching pigments etc., Complete. Size of Tile 500x500 mm	Sqm	1163.00	Rupees One Thousand One Hundred Sixty Three Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner

21	58.50	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length andb jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters. 80x1.25 mm M.S. laths with 1.25 mm thick top cover including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	Sqm	2885.00	Rupees Two Thousand Eight Hundred Eighty Five Only
22	600.00	Supplying heavy gauge PVC conduit pipe..... dia confirming to IS 2509 with suitable size benda, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall stone structure or rawl plugs in case of brick walls and cement plastering damaged portion using heavy gauge saddles at an interval of 700mm using NF screws.	m	84.00	Rupees Eighty Four Only
23	600.00	Supplying..... mm dia 2mm/2.5mm thick heavy gauge PVC conduit pipe with suitable size bends, metal/PVC junction boxes adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures. run with 18SWG GI fish wire wherever necessary.	m	73.00	Rupees Seventy Three Only
24	456.00	Groove cutting in the wall supplying.....dia 2mm/2.5mm thick heavy gauge PVC Conduit Pipe with bends, metal junction boxes adhesive paste etc., and bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out conduit wherever necessary.	m	84.00	Rupees Eighty Four Only
25	36.00	Supplying and fixing sheet metal box made out of 18 SWG sheet metal with necessary holes for cable/conduit entry as required with one coat of approved make etc. c) 135x75x65mm	each	137.00	Rupees One Hundred Thirty Seven Only
26	36.00	d)180x90x65mm	each	162.00	Rupees One Hundred Sixty Two Only
27	36.00	e)200x90x65mm	each	177.00	Rupees One Hundred Seventy Seven Only
28	60.00	Supplying and fixing PVC/metal conduit accessories.(3/5) (ELE SR 2021-22 Page-1, Item-1.5) 1. Special type junction box b)25mm junction box	each	53.00	Rupees Fifty Three Only
29	60.00	2. Deep junction box c) 32mm deep junction box	each	72.00	Rupees Seventy Two Only
30	12.00	Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, necessary masonry patch work cpmplete. a)12xx"12"x3" (330x300x76mm	m	117.00	Rupees One Hundred Seventeen Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner

31	12.00	b)12"x9"x3" (300x228x76)	m	110.00	Rupees One Hundred Ten Only
32	120.00	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using copper PVC insulated multi strand 2x1.5Sqmm copper wire with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. compelete for each outlet. a) Short point up to 3Mtr from tapping point to out let via switchEach point	each	288.00	Rupees Two Hundred Eighty Eight Only
33	120.00	b) Medium point above 3Mtr up to 6Mtr from tapping point to out let via switch (Each point)	each	403.00	Rupees Four Hundred Three Only
34	120.00	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using copper PVC insulated multi strand 2x1.5Sqmm copper wire without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. a) Short point up to 3Mtr from tapping point to out let via switch box	each	262.00	Rupees Two Hundred Sixty Two Only
35	120.00	b) Medium point above 3Mtr up to 6Mtr from tapping point to out let via switch box	each	377.00	Rupees Three Hundred Seventy Seven Only
36	108.00	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. I.Group-A e) 6Moudule	each	255.00	Rupees Two Hundred Fifty Five Only
37	60.00	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate.. I.Using Group "A" materials a) 6Amps one way.	each	92.00	Rupees Ninety Two Only
38	24.00	i) 32Amps DP switch	each	392.00	Rupees Three Hundred Ninety Two Only
39	180.00	j) 6/16Amps universal socket	each	260.00	Rupees Two Hundred Sixty Only
40	24.00	Supplying and fixing 32Amps security and energy saving DP switch with key tag suitable to operate on 230 Volts, 50Hz AC supply &completely wired on existing box. I.Using Group "A" materials	each	781.00	Rupees Seven Hundred Eighty One Only
41	1800.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments. a. 1 sqmm.	m	19.00	Rupees Nineteen Only
42	1800.00	b. 1.5 sqmm	m	27.00	Rupees Twenty Seven Only
43	2400.00	C.6 sqmm	m	91.00	Rupees Ninety One Only

Executive Engineer
RRNagara Division
BBMP

Signature of the contractor

Scanned with CamScanner

44	240.00	Supplying and fixing of PVC casing and capping on the wall or ceilng using necessary materials like bends, screws at an interval of 300mm ..... Etc as required a) 20mm	m	28.00	Rupees Twenty Eight Only
45	180.00	Supplying PVC/GI flexible conduit pipe.....mm dia fixing on surface over inverted wooden plugs or phill plugs or rawl plugs and clamped using heavy gauge saddles at an interval of 300mm using NF screws and either end of the pipe terminated completely a) 20mm	Nos	26.00	Rupees Twenty Six Only
46	120.00	Extra for supplying 4mm thick white plastic plate and covering for junction boxes of size 110mm conduit using necessary machine screws. b) 110mm	Nos	12.00	Rupees Twelve Only
47	120.00	Supplying a 50mm wooden plug, tapered from 50x50mm to 25x25mm and fixing by using binding wire before concreting a roof slap.	Nos	8.00	Rupees Eight Only
48	48.00	Supplying and fixing of slim box fitting, made out of CRCA Sheet metal body with locking type holder completely wired. Excluding Ballast & Flouresent Tube. 1 x 4' Tube light fitting.	each	324.00	Rupees Three Hundred Twenty Four Only
49	48.00	Supplying and fixing of T5 Fluorescent Tube with 14W power consumption with low 3mg Mercury content & below 40% glass content than T8 lamp & 20% less phosphor coating than T8 with initial lumen on 1350 (for 3000-6500 deg Kelvin), rated Avg life (12 Hr. Cycle) of greater than 35000 burring hours. Operating voltage range from 180V to 265V, 50Hz AC power Supply 28 watts Lamp	each	180.00	Rupees One Hundred Eighty Only
50	24000.00	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS: 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	Ltr	9.00	Rupees Nine Only
51	216.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 25 mm nominal dia Pipes	mtr	363.00	Rupees Three Hundred Sixty Three Only
52	180.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 32 mm nominal dia Pipes	mtr	452.00	Rupees Four Hundred Fifty Two Only
53	24.00	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber 150 x 100 mm size P type With Non Modular common burnt clay bricks of designation 3.5 & with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight or cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design:	Each	2643.00	Rupees Two Thousand Six Hundred Forty Three Only
54	24.00	Raw water Feed pump with starter,Type-Horizontal ,Centrifugal Make-Kirloskar/Beacon weir/Sumo/CNP(SS),Material of Construction-Cast Iron,Head-36 MWC. Motor-3.0HPthree phase.Starter-L&T Siemen make push botton type DOL Starter	Nos	25603.00	Rupees Twenty Five Thousand Six Hundred Three Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner

55	24.00	Multi graded sand filter,type-verticle,Floor Mounted,Make-pentair/structural/ION EXCHANGE(INDIA) LTD/Zeolite/Aquario,min.operating Pressure 2.0kg/cm2,Max. Operating Pressure -3.5kg/cm2, Treatment Flow Rate-6000liters/Hr,Type of valve size-Multiport,50NB,make-UKL/Initiative,Filtering Media -Gravel,Graded Sand & Pebble	Nos	34485.00	Rupees Thirty Four Thousand Four Hundred Eighty Five Only
56	12.00	Activated carbon Filter type-Verticle,Floor Mounted,Make-pentair/Structural/ION EXCHANGE(INDIA) LTD/Zeolite/Aquario,min.operating Pressure 2.0kg/cm2,Max. Operating Pressure -3.5kg/cm2, Treatment Flow Rate-6000liters/Hr,Type of valve size-Multiport,50NB,make-UKL/Initiative,Filtering Media -Gravel, Activated Carbon & pebbles	Nos	65313.00	Rupees Sixty Five Thousand Three Hundred Thirteen Only
57	12.00	Water Softner,type-Verticle,Floor Mounted,Make-pentair/Structural/ION EXCHANGE(INDIA) LTD/Zeolite/Aquario,min.operating Pressure 2.0kg/cm2,Max. Operating Pressure 3.5kg/cm2, Treatment Flow Rate-6000liters/Hr,Type of Resin INDION 220Na or Thermax T40	Nos	64790.00	Rupees Sixty Four Thousand Seven Hundred Ninety Only
58	12.00	Antiscalant Dosing System,Equipment Required-Electronic Dosing Pump with Solution Tank,make-Ion Exchange (I) Ltd.,/ASIA LMI/Zeolite,Material of Construction-PP(Polypropelene),Discharge @Max Back Pressure-2.88litr/Hr @8bar,Discharge@Nominal Back Pressure=3.12Lit/Hr @ 4Bar,Chemical to be dosed-INDION Antiscalant	Nos	88825.00	Rupees Eighty Eight Thousand Eight Hundred Twenty Five Only
59	12.00	Accessories for Dosing System,Solution Tank-One No,Volume-100Litres,Material of Construction-HDPE,Tank level Switch-One No.	Nos	43890.00	Rupees Forty Three Thousand Eight Hundred Ninety Only
60	12.00	Reverse Osmosis System,Type-Horizontal Skid,Floor Mounted,Permeate water-Minimum 2000litr/hr,Maximum Permissable TDS in feed (PPM)-2500.	Nos	93005.00	Rupees Ninety Three Thousand Five Only
61	12.00	Pressure Vessel,Material of Construction-FRP,Make-Advance Composite/Code Line.	Nos	88825.00	Rupees Eighty Eight Thousand Eight Hundred Twenty Five Only
62	12.00	Membrane, Type-Brackish water . Nos required-Three.Make-TORAY JAPAN /Hydranautics/Filmtec/Tricep	Nos	91960.00	Rupees Ninety One Thousand Nine Hundred Sixty Only
63	12.00	High pressure pump,Type- verticle,multistage,Make-GRUNDFOS,MOTOR-7.5 HP 3Phase, Model-CRN series,Material of construction-SS316,starter-L&T/Seimens make push botton type DOL starter	Nos	57475.00	Rupees Fifty Seven Thousand Four Hundred Seventy Five Only
64	12.00	Micron Filter,Type -JUMBO,Material of construction of housing-poly propelene	Nos	81510.00	Rupees Eighty One Thousand Five Hundred Ten Only

Executive Engineer
RRNagara Division
BBMP

Signature of the contractor

Scanned with CamScanner

65	12.00	Instruction, Wet panel -Ms powder coated., Mounted on R.O> skid, Low pressure switch-one No,High Pressure Switch-one, Digitalconductivity Meter wiyh sensor , Indon brand-one No , ON/OFF selector Switch -one No, High pressure System Pressure Gauge - one No, Auto Flush Timer -one No, Indication Lamps -one No, product Flow Meter- one No, Reject Flow Meter-one No,Reject Re-circolation Meter-one No,Alarm-one No	Nos	89870.00	Rupees Eighty Nine Thousand Eight Hundred Seventy Only
66	12.00	pH correction dosing System, Equipment Required-Electronic Dosing Pump with solution Tank, Make-Ion Exchange(1) Ltd.,/ASIA LMI/Zeolite,Material of construction -PP, Discharge @ max . Back Pressure-2.88 Lit/Hr@8Bar.Discharge@Nominal Back Pressure-3.12 Lit/Hr@4Bar,Frequency-100 Strokes / Min, Chemical to be dosed-PH Booster	Nos	86735.00	Rupees Eighty Six Thousand Seven Hundred Thirty Five Only
67	12.00	Solution Tank with level switch, Solution Tank-one No, Volume-100 Liters. Material of construction-HDPE. Tank levelswitch-one No	Nos	15675.00	Rupees Fifteen Thousand Six Hundred Seventy Five Only
68	12.00	Inter-connecting pipe work ,Raw water tank to feed pump suction and feed pump delivery to R.O. Inlet (up to High pressure pump in let)and RO outlet to Treated water tank-food Grade PVC pipe 40mm NB, Make-Finolex/ supreme,High pressure pump outlet to membrane inlet-ss pipe of required size, Approximate Length-35.0 Metre	Nos	81510.00	Rupees Eighty One Thousand Five Hundred Ten Only
69	12.00	Ultra violet system, Model-UVS-20,Make-Ion Exchange (I) Ltd.,/ASIA LMI/Zeolite,ALFA Flow rate-2000L/H	Nos	77853.00	Rupees Seventy Seven Thousand Eight Hundred Fifty Three Only
70	12.00	RO water strong tank, 2000 ltrs SS tank, to store RO water with required nozzles	Nos	83600.00	Rupees Eighty Three Thousand Six Hundred Only
71	12.00	Wending Machine ,Digital Swiping Card Type	Nos	36575.00	Rupees Thirty Six Thousand Five Hundred Seventy Five Only
72	12.00	Geophysical investigation at site for sinking borewells for supplying drinking water to the habitation either through the Hand Pump MWS or P.W.S.S, by vertical electrical sounding by adopting Venner or Schlumbergers's method, including reconnaissance survey of geological formation. Geophysical investigation of existing ground water in the vicinity, its quality, quantity and acceptability of the users, indicating the location of the site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 metre in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instruments	No	5372.00	Rupees Five Thousand Three Hundred Seventy Two Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner

73	600.00	Sinking of Borewell of 165mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burdern upto 20 m. Fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicle, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (Excluding cost of casing pipes, collars, cap etc., complete) 0 to 50 m	Rmt	363.00	Rupees Three Hundred Sixty Three Only
74	600.00	50 to 100 m	Rmt	462.00	Rupees Four Hundred Sixty Two Only
75	600.00	100 to 150 m	Rmt	477.00	Rupees Four Hundred Seventy Seven Only
76	600.00	150 to 200 m	Rmt	560.00	Rupees Five Hundred Sixty Only
77	600.00	200 to 250 m	Rmt	663.00	Rupees Six Hundred Sixty Three Only
78	600.00	250 to 300 m	Rmt	732.00	Rupees Seven Hundred Thirty Two Only
79	600.00	300 to 350 m	Rmt	862.00	Rupees Eight Hundred Sixty Two Only
80	600.00	350 to 400 m	Rmt	941.00	Rupees Nine Hundred Forty One Only
81	240.00	400 to 420 m	Rmt	1180.00	Rupees One Thousand One Hundred Eighty Only
82	144.00	Providing and fixing 250mm dia PVC (casing pipe)	Rmt	2717.00	Rupees Two Thousand Seven Hundred Seventeen Only
83	600.00	Supply of ISI mark 175mm nominal bore,plain and steel casing pipe grade of steel Fe 410 of wall thickness conforming to IS 4270-2001 and latest ammendments, electrical resistance welded steel tubes, material and conforming to IS 1387-1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5-7m both ends.threaded conforming to IS 554-1985 one end fixed with socket conforming to IS 4270-2001 and the other end with screwed pipes all shall be responsibaly free from defects. The tubes shall be responsible straight end should be with ISI marking weighing 25.10kg/m.prices include Collar-Medium duty.	Rmt	2020.00	Rupees Two Thousand Twenty Only

Executive Engineer
RRNagara Division
BBMP

Signature of the contractor

Scanned with CamScanner

84	100.00	Providing and fixing MS casing collars as per IS 1239 (part-II) 1982 with all latest amendments if any for any dia. The thickness of plate used for covering one end shall be 3mm (minimum). The dimensions of caps and colars shall be strictly as per IS 1239 (Part-II) 1982 with all amendments	Each	157.00	Rupees One Hundred Fifty Seven Only
85	12.00	Providing 175mm dia Bore Cap CE (M)	No	105.00	Rupees One Hundred Five Only
86	12.00	Atalanta suguna CRI KIRLOSKAR and other equipments pumps 10.00 HP/7.5 KV (20 stage)	No	52203.00	Rupees Fifty Two Thousand Two Hundred Three Only
87	4185.00	Providing and fixing in trenches galvinised/mild steel tube 50mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for seperately) including cost of all materials, labour charges,HOM of equipment and testing complete as per specifications. Specification No. KBS 13.2.14/13.6	Rmt	430.00	Rupees Four Hundred Thirty Only
88	8310.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable maufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 to IS 8130-1984 and virgin grade PVC insulation and power coating extruded PVC sheathed suitable for working voltage upto 1100 volts with specified IS 694:1990 and confirming to the attwached GTP of group A 3CX4.0 sq mm	Rmt	132.00	Rupees One Hundred Thirty Two Only
89	12.00	Providing and fixing in position 50mm Nominal bore non-return valve vertical type of approved make including cost of all materials,labour and HOM of equipment with all leads complete as per specifications.	No	1406.00	Rupees One Thousand Four Hundred Six Only
90	12.00	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) :	No	624.00	Rupees Six Hundred Twenty Four Only
91	12.00	Spplying and fixing 50mm GI Elbow.	No	117.00	Rupees One Hundred Seventeen Only
92	12.00	Spplying and fixing 50mm GI Nipple	No	109.00	Rupees One Hundred Nine Only
93	696.00	Spplying and fixing 50mm GI Hose colleres	No	108.00	Rupees One Hundred Eight Only
94	12.00	Supplying and fixing 20" x 20" x 2.5" polished wood board made of not less than 15mm thick plank on both the sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc.,	No	316.00	Rupees Three Hundred Sixteen Only
95	12.00	Supplying and fixing miniature circuit breakers on existing MCB distribution board using necessary fixing materials and 'C' type curve indicator ON/OFF energy cross-3 with short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.6-32 A TPN	No	1857.00	Rupees One Thousand Eight Hundred Fifty Seven Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner

96	12.00	Supplying of TPST with rewirable porcelain channels in SM encloser made out of 14 SWG powder coated point of approved colour 32 amps	No	2031.00	Rupees Two Thousand Thirty One Only
97	12.00	Supplying and fixing LED type panel board indicating lamp with required colour suitable for 220 V AC 50 HZ 12/24 V DC	No	485.00	Rupees Four Hundred Eighty Five Only
98	12.00	Suppling fully automatic star delta starter unit push button type with suitable wires 2 conductors and adjustable thermal timer mounted on a common base plate held in steel enclosure for use on 400/440 volts phase and wired after fixing to the existing wooden board for motor. upto 12.5HP	No	7223.00	Rupees Seven Thousand Two Hundred Twenty Three Only
99	12.00	Supplying and fixing single phase preventer using necessary wires over an existing panel board suitable for motar up to 20 HP capacities.	No	841.00	Rupees Eight Hundred Forty One Only
100	240.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade multistrand copper conductor single core wire in open or concealed system of wiring as per IS 694:1990 & conforming to the attached GTP of group A. 4 sqmm	Mtrs	62.00	Rupees Sixty Two Only
101	48.00	Supplying fixing and wiring heavy duty low voltage capacitors conforming to IS 2834 phase 400/440 volts grade, for power factor improvement of rotating machinery.	No	451.00	Rupees Four Hundred Fifty One Only
102	12.00	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cotouts and other equipments on the meter board using 40mm dia 2.90 thick GI pipe 2.5 mtr long buried in a pit... The pit should be filled with equal proprotion of salt and charcoal 150mm alround the pipe to complete depth. The connection from the to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia	No	3135.00	Rupees Three Thousand One Hundred Thirty Five Only
103	96.00	Digging of trench of 0.36mtrs deepx0.5 mtrs wide refilling the trench to the required gorund level and consolidating etc., complete	Mtrs	107.00	Rupees One Hundred Seven Only
104	120.00	Supplying laying 1.1 KV class LT UG cable having aluminium conductor PVC insulated extruded inner shethed galvanised steel strip (excep 2cx 10 sqmm wire armoured) confirming to IS-3975:1990 (No. of strip indicated in GTP) and extruded PVC outer sheathed armoured cable with specified IS-1554,part-1:1988 and confirming to the attached GTP of group A 4 core 16 sq mm	Mtrs	157.00	Rupees One Hundred Fifty Seven Only
105	300.00	Labour charge for laying 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe/ on wall / on poles as required in existing trench/duct. 6 sq mm to 16 sq mm	No	12.00	Rupees Twelve Only
106	24.00	Supplying and fixing class-A(medium duty) GI pipe wall thickness not less then 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1KV class 40mm	Rmt	350.00	Rupees Three Hundred Fifty Only
107	12.00	Supplying and fixing LT cast iron pot heads suitable for 1.1KV class UG cable filled with necessary bitumen / insulating compound complete with terminals,clamps bolts and nuts and washer etc.,complete for 16 sq mm as per specifications.	No	282.00	Rupees Two Hundred Eighty Two Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner

108	36.00	Supplying and fixing porcelain fuse channel with cut out on the existing wooden block and wiring complete 63 amps	No	389.00	Rupees Three Hundred Eighty Nine Only
109	78.16	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separately	Cum	485.00	Rupees Four Hundred Eighty Five Only
110	216.00	Earth work excavation for pipeline trenches in all kinds of by mechanical means above 600 mm trench width as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & bonding rods at every 100 mm whevere necessary as directed, removal of slumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required , utilising the available excavated earth locally for the work and all other appurtenances to complete in the following strata.	Cum	393.00	Rupees Three Hundred Ninety Three Only
111	1326.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (external work) - 50mm nominal OD pipes	Mtr	807.00	Rupees Eight Hundred Seven Only
112	132.60	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 25 to 40 mm nominal bore	Each	541.00	Rupees Five Hundred Forty One Only
113	120.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling & testing of joints complete. (external work). - 20mm nominal OD pipes	Mtr	247.00	Rupees Two Hundred Forty Seven Only
114	1500.00	Providing and fixing to wall, ceiling and floor Medium density polyethylene pipes 6.00 kgf/sq cm working pressure 25mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.15.1 / 13.9	Mtr	143.00	Rupees One Hundred Forty Three Only
115	151.20	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. Including cost of all labour complete as per specifications	Cum	140.00	Rupees One Hundred Forty Only
116	142.96	Loading and unloading of stone boulder/stone aggregates/sand/kanker/ moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1	Cum	102.00	Rupees One Hundred Two Only

Executive Engineer
RRNagara Division
BBMP

Signature of the contractor

Scanned with CamScanner

117	12.00	Providing and fixing Brass full way valve gate with C.I. wheel of approved quality (screwed end) 65 mm nominal bore	Each	1598.00	Rupees One Thousand Five Hundred Ninety Eight Only
118	132.60	Providing and fixing brass stop cock of approved quality :	Each	375.00	Rupees Three Hundred Seventy Five Only
119	89.51	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregates	Cum	6812.00	Rupees Six Thousand Eight Hundred Twelve Only
120	12.00	BESCOM deposit Charges and miscellaneous	No	12540.00	Rupees Twelve Thousand Five Hundred Forty Only
121	13.12	Providing and laying in position Reinforced cement concrete M20 Using 20 mm nominal size graded crushed coarse aggregates for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately)	Cum	7066.00	Rupees Seven Thousand Sixty Six Only
122	3.24	Providing and laying in position Reinforced cement concrete M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/ trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement, dowel bars & formwork to be paid separately)	Cum	7817.00	Rupees Seven Thousand Eight Hundred Seventeen Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner

123	14.42	Providing and laying in position Reinforced cement concrete M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates for all Super structures of building , Road works ,Water works ,Irrigation works & super structure works of bridges upto 3.50 m height .The granite/ trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators .The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications .(The cost of steel reinforcement, dowel bars & formwork to be paid separately)	Cum	8527.00	Rupees Eight Thousand Five Hundred Twenty Seven Only
124	3.85	Supplying, Fitting and Placing TMT Fe 500 & above Reinforcement in Foundation / Substructure / Superstructure complete as per Drawing and Technical Specifications.	Cum	96634.00	Rupees Ninety Six Thousand Six Hundred Thirty Four Only
125	31.21	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	6152.00	Rupees Six Thousand One Hundred Fifty Two Only
126	192.75	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x200x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572 2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	Sqm	1375.00	Rupees One Thousand Three Hundred Seventy Five Only
127	474.81	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonary including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	344.00	Rupees Three Hundred Forty Four Only
128	38.28	Providing 12 mm cement plaster with cement mortar 1:4 (1 cement: 4 fine sand) to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	245.00	Rupees Two Hundred Forty Five Only
129	513.09	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two coat applied @ 1.67 ltr/10 m^2 over and including priming coat of exterior primer applied @ 2.20 kg/10 m^2) with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	156.00	Rupees One Hundred Fifty Six Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner

130	42.78	Providing and laying water proofing treatment to the Roof with PU based single component elastomeric pure polyurethane based coating on New terrace/Chajjas/Sunken portion of WC Bathroom, cold applied PU waterproofing membrane that is highly elastic with elongation greater than 400% and tensile strength greater than 2MPa as per ASTM D412. The waterproofing membrane to be applied in 2coats @ 1.6kg per m2 to achieve final DFT (dry film thickness) of 1mm including prime coat of epoxy primer @150 g per m2 and protection with 120gsm Geo-textile over the waterproofing membrane. The finished cost to include surface preparation, making coving at Junction, Bore Packing, treatment of construction joints completely as per specification & with a 10 years warranty on product & work from certified manufacturers as per the direction of the Engineer In charge.	Sqm	856.00	Rupees Eight Hundred Fifty Six Only
131	128.31	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ m2 including grouting the joints with white cement and matching pigments etc., Complete. Size of Tile 500x500 mm	Sqm	1163.00	Rupees One Thousand One Hundred Sixty Three Only
132	19.50	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length andb jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters. 80x1.25 mm M.S. laths with 1.25 mm thick top cover including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	Sqm	2885.00	Rupees Two Thousand Eight Hundred Eighty Five Only
133	4839.58	Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work.. In all kinds of soils upto 300 mm depth	Cum	168.00	Rupees One Hundred Sixty Eight Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned with CamScanner

134	2903.75	Construction of Granular Sub-Base of required grading as per design mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401. Granular Sub-BasePlant Mix Method. Materia.	Cum	2698.00	Rupees Two Thousand Six Hundred Ninety Eight Only
135	3387.71	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. Wet Mix Macadam (Plant mix method)	Cum	2752.00	Rupees Two Thousand Seven Hundred Fifty Two Only
136	19358.32	Providing and applying primer coat with SS1 grade Bitumen Emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.90 kg per m2 using mechanical means. .Issue Rate 07/07/2022	Sqm	48.00	Rupees Forty Eight Only
137	967.92	Bituminous Macadam Grading - II for traffic <20 MSA Providing and laying Bituminous Macadam with 40/60 TPH capacity hot mix plant using crushed aggregates of specified grading premixed with bituminous binder VG-30 @ 3.4% by weight of mix, transported to site, laid over a previously prepared surface with mechanical paver finisher to the required grade, level and alignment and rolled as per clauses 501.6 and 501.7 to achieve the desired compaction .Issue Rate 07/07/2022	Cum	8537.00	Rupees Eight Thousand Five Hundred Thirty Seven Only
138	64527.75	Providing and applying tack coat with RS1 Bituminous Emulsion using emulsion pressure distributor at the rate of 0.20 kg/m2 on the prepared bituminous surface cleaned with mechanical broom	Sqm	13.00	Rupees Thirteen Only
139	2581.11	Bituminous Concrete Grading II for traffic <20 MSA Providing and laying Bituminous Concrete with 40/60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 5.4 per cent of mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specificationclause No. 507 complete in all respects(.Issue Rate 07/07/2022	Sqm	12197.00	Rupees Twelve Thousand One Hundred Ninety Seven Only
140	2320.90	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous SurfaceProviding and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 g/m2 area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35:2015.The finished surface to be level, uniform and free from streaks and holes	Sqm	549.00	Rupees Five Hundred Forty Nine Only

Executive Engineer
RRNagara Division
BBMP

Signature of the contractor

Scanned with CamScanner